THE MAGAZINE OF THE AMERICAN SOCIETY OF CIVIL ENGINEERS

\*\*\*\*\*\*\*\*\*\*\*\*\*CAR-RT LOT\*\*R-016 lalllamallalalalalal 002868730000 CE200804 Ian F. Smith, PE, M.ASCE Wetland Studies & Soultions Inc 5300 Wellington Branch Drive Suite 100 Gainesville VA 20155-4003

P0051 94950 30732 V9001 A CONTRACTOR OF THE PROPERTY O

#### ENVIRONMENTAL ENGINEERING

# Mitigation Bank Finances Major Stream Restoration in Northern Virginia

emand for stream restoration typically far exceeds the funds available for such efforts. For this reason restoration projects are often piecemeal undertakings, focusing only on the most degraded stream sections rather than comprehensively addressing an entire waterway. An exception to this rule, however, can be found in Reston, a planned community of approximately 60,000 residents in Virginia's Fairfax County. Construction work recently began there in an effort to restore three of Reston's streams along their entire lengths—a total of 14 mi (23 km). Yet instead of draining the community's coffers, the project will cost Res-

ton nothing, thanks to its innovative partnership with Virginia's first urban stream mitigation bank.

The Northern Virginia Stream Restoration Bank was formed in 2003 by Wetland Studies and Solutions, Inc. (wssi)—a water and natural resources consulting firm headquartered in Gainesville, Virginia—and the Peterson Companies, a real estate developer based in Fairfax, Virginia, which provides financial and legal support. Approved by the U.S. Army Corps of Engineers and the Virginia Department of Environmental Quality (DEQ) in 2006, the bank has sold approximately 200,000 "stream condition units" (SCUS)—credits that

WSSI uses to determine how much restoration work it will conduct—to public and private entities whose development projects have had a deleterious effect on streams in northern Virginia, explains Michael Rolband, P.E., M.ASCE, the president of wssi.

By purchasing scus from the restoration bank, developers obviate the need to implement mitigation measures on streams harmed by their work. The number of scus that a developer must purchase depends on the quality of the affected stream and the extent to which the developer's project will affect it. Using an assessment technique approved by the Corps and the Virginia

DEQ, WSSI assigns a score to a stream that will be affected by a development project. High-quality streams, that is, streams in a relatively pristine condition, receive high scores while streams in poor condition receive low scores. In turn, the score dictates how many SCUS a developer must purchase per lineal foot of stream to be affected. In short, developers whose projects affect high-scoring streams must purchase more SCUS than those affecting low-scoring streams.

For every SCU sold, wssI carries out restoration work on streams within the region. The more intensive its restoration effort, the more SCUs the company can claim. "Based on what we're doing, we get a different number of credits per foot," Rolband says. For example, total reconstruction of a stream—similar to what the company is doing in Res-

ton—provides the most scus per foot of restored stream, he says. By contrast, simply planting trees beside a stream would confer a "minimal number of scus per foot," Rolband says.

Approximately 65 percent of the scus sold thus far have been purchased by a handful of large public entities, Rolband says. For example, roughly half of the total scus sold so far went to Washington Dulles International Airport, which needed to offset harm to the environment caused by the construction of a new runway. The remaining 35 percent of the scus have been purchased mainly to provide mitigation for numerous private developments.

wssi decided to restore streams in Reston, Rolband says, because most of the land through which the streams flow is owned by the Reston Association, the community's homeowners' association. This arrangement vastly simplifies efforts related to such issues as right-of-way. However, Reston also benefited from the existence of a watershed management plan developed for the Reston Association by GKY and Associates, Inc., of Chantilly, Virginia. "We had the plan in hand," says Larry Butler, the association's director of parks and recreation, when wss1 and the Reston Association began discussions regarding a partnership.

wssı ultimately hopes to restore all 26 mi (42 km) of Reston's streams, Rolband says. Thus far, however, the firm has received regulatory approval to repair only 14 mi (23 km). The work will entail restoring the entire lengths of the three streams—Snakeden Branch, the Glade, and Colvin Run—named in the watershed management plan as the ones most in need of restoration.

vastly issues ceston e of a loped y and ginia. Larry or of I and iscus-

ore all eams, r, the proval work ths of anch, ned in

Established in the 1960s, Reston was developed with a "fantastic vision" that included the use of significant natural buffer areas around the community's streams, Rolband says. Unfortunately for its streams, however, Reston was constructed with little regard for storm-water management, except for the construction of four large lakes. Traditional curb and gutter systems, designed to remove storm water from developed areas as quickly as possible, were connected to pipes or open concrete flumes that convey storm water directly to the nearest stream's floodplain, essentially bypassing the buffers along the waterways. "Since there was no detention or infiltration, there is a huge increase in the volume of water, plus a huge increase in velocity," Rolband says. "That water has way more energy now."

The resulting erosion has converted large stretches of the streambeds into vertical "canyons" devoid of vegetation, Rolband says. Compounding the problem, the heavily incised streambeds prevent all but the highest flows from overtopping the banks, which would dissipate some of their energy. As the large and fast flows from the streams erode the banks, sediment washes downstream, accumulating in Reston's lakes and degrading the water quality there. The Reston Association, which currently must dredge its lakes every few years, expects to see its dredging costs decrease "significantly" once the restoration projects are complete, Butler says.

Three years ago wssi installed flow gauges and rain gauges along the three streams to accumulate data for use in designing the restoration projects. Because most of the data are associated with small storms, wsst is using actual flow data to determine a stream's appropriate channel size during periods of low flow. To determine the appropriate channel sizes to accommodate an event that would fill the rivers to their banks, the firm is relying on published data on streams in the Piedmont Physiographic Province, data that wsst adjusts to account for the levels of imperviousness in each stream's watershed.

The designs for each stream must contend with "a lot of constraints," Rolband says, including sewer lines, pedestrian bridges, and numerous trees. Before beginning design work, wssi surveyed the streams and their accompanying features. Reston required that wssi include in its surveys all trees with a diameter greater than 4 in. (102 mm) located within a certain distance from the

streams. Thus far the firm has included more than 30,000 trees in its surveys.

To reconnect the streams to their floodplains, the vertical stream banks will be graded to flatten their slopes. The graded material will then be mixed with rock, gravel, and sand to form "constructed riffles" in the stream. These riffles are designed to have enough shear strength to resist erosion, Rolband says. To minimize shear stress on the stream banks, such structures as cross-vanes and I-hook vanes made of rock or wood will be used to deflect water from the banks and direct it toward the center of the stream. The graded slopes and the structures facilitate the reestablishment of vegetation. Native shrubs will be planted along the stream edges, while trees will be planted higher up on the banks and in the floodplain. Biodegradable coir fabric will be placed along the banks to prevent erosion until vegetation takes hold.

To address problems resulting from the existing system for conveying runoff to the floodplains, wssi is removing portions of the flumes in certain locations. In places where the structures will remain, Rolband says, a series of rock-lined step pools will be built to absorb the water's energy before the

Construction work on the three uppermost reaches of Snakeden Branch began in February and is scheduled to be completed this month. The next eight reaches will be restored this summer, followed by the remaining six reaches in the fall. The design work on the restoration of the Glade is under way, and construction is slated to begin in early 2009; the design work on Colvin Run will begin this fall, with construction scheduled to start one year later.

All told, wssi has budgeted \$70 million to restore the three streams, a figure that includes a plan to monitor

and maintain the streams for 10 years after construction. To cover any problems that might arise after the monitoring period, the Reston Association will receive 5 percent of the mitigation bank's sales revenue. What is more, the Friends of Reston-a nonprofit organization that works with the Reston Association-will receive approximately \$800,000, says Charles Veatch, an officer of the group and the president of the Reston-based Charles A. Veatch Company, a real estate and development firm. Aside from the many benefits it is conferring on Reston, the Northern Virginia Stream Restoration Bank will improve water quality in downstream waterways, including the Potomac River and the Chesapeake Bay, Veatch notes. "It's an outstanding example of what can be done elsewhere in the country," he says.

—Jay Landers